

Linden, NJ

NuStar Linden Terminal - Tanker Dock Repairs



Owner: NuStar Energy

Client/Engineer: S.T. Hudson Engineers, Inc.

Year Complete: 2009

Scope of Work: Demolition, Construction

Project Cost: \$1.25 Million

Demolition and rehabilitation of an existing 37' diameter sheet pile cell. The work included removing the existing 4' thick (350-ton) cap, re-ringing the new sheet pile (80-PS 31's), placing concrete fill inside the cell, pouring new reinforced concrete cap, and the installation of deck fixtures and hardware.

The work was completed on schedule, working two (2) shifts for four (4) weeks and was completed Incident and Injury Free (IIF).